

# Beachflag Fiber Wind

---

## *Delivery specifications*

### PDF format

- Do not place any cutting lines or frames around the printable image.
- Convert all fonts into letter outlines.
- Remove all invisible layers from the layout.

### Use of colour

- Use CMYK colours. No LAB colours.
- For the deepest black, use the following colour codes: CMYK 86/85/79/100 or RGB 0/0/0. When files with both vectors and photos (bitmaps) are used, also use these colour codes in the photos. Otherwise colour differences may arise within the images  
***Note: colours can deviate slightly when printed on fabric. A test print is available on special request.***

### Resolution


- We advise a resolution of 70 to 120 dpi (End format).  
*(If the image in the file has 10% of the size of the end format, the image in the file must have a resolution of 700 to 1200 dpi)*

### Dimensioning

- We always communicate in the sequence width first, then height (w x h).
- Files delivered in the correct ratio (w x h) will automatically be scaled to the requested format.
- Deviations in the ratio (w x h) up to 1.5% are automatically adjusted to the ordered size. If the deviation exceeds 1.5%, we will contact you.
- Image dimensions can deviate slightly due to stretch, shrinkage or the elastic properties of the material.

# Beachflag Fiber Wind

## Template



### File set-up



The **blue line** is the outline of the file that is finally send through. This includes 0,5 cm bleed. The tunnel is also printed along.



Tailoring is done on the **red line**. This is the final net size.



Important text and images should be placed within the **green line** because of the confection.



**Black line:**  
Tunnel.



**Orange line:**  
Visible size after confection.

### Sizes



47 x 156 cm  
65 x 194 cm  
78 x 285 cm  
78 x 403 cm


### Sizes including 0,5 cm bleed

51 x 161 cm  
69 x 199,5 cm  
83 x 287,5 cm  
84 x 405,5 cm

### Supplying of file

1. Please remove all sizes and lines (red, green, blue, orange and black).
2. Supply on real size in PDF via e-mail / WeTransfer.






**BFFW-SG**

47 x 156 cm

Scale 1:10

Supply the file on:

**51 x 161 cm**



The image shows a technical drawing of a curved surface, possibly a dome or a large arch. It features several concentric curves: a solid black line, a dashed blue line, and a dashed green line. The drawing is enclosed in a rectangular frame with a dashed blue border. The text is centered within the drawing area.


**BFFW-MG**

65 x 194 cm

Scale 1:10

Supply the file on:

**69 x 199,5 cm**



**BFFW-LG**

78 x 285 cm

Scale 1:10

Supply the file on:

**83 x 287,5 cm**

**BFFW-XLG**

78 x 403 cm

Scale 1:10

Supply the file on:

**84 x 405,5 cm**

